

SONEPUR STP AND I & D PROJECT

1	<p>It is observed that the ground levels representing in the Longitudinal section of the pipe line (referred to 190) & Hydraulic Process of STP (referred to 100) are different. Meanwhile in the provided prebid replies, the HFL of Gandaki River is provided with another datum level (50.320). Hence, we request you to correlate the level particulars and provide with same datum.</p>	<p>In I&D scheme, Survey had been done referring to a temporary level on the Railway line considering 200 m because that time no permanent benchmark was available. Hence levels are ranging from 200 to \pm 6m. In this context, it may be noted, for the design purpose the levels shown had not caused any problem. In another context, network part will be awarded in DBOT. Hence, Contractor have to do resurvey, redesign for same location.</p> <p>For STP, treatment technology will be open type. Hence, hydraulic profile of STP part will change according to technology. Also, STP will be awarded as a DBOT. Hence, Contractor has to do resurvey, re design and according to same Hydraulic profile will also change. However, STP land is situated above HFL.</p>
2	<p>Item no: 9, Table 12 in the BOQ of Network, vide page no: 91 of 524, it is mentioned that BUIDCo., will be supplying the MS sheet piles and the contractor has to include the hire charges and carriage charges from departmental godown to work site but nowhere in the tender it is mentioned that what will be hire charges & what would be the location of the departmental stores and lead. We therefore request you to provide us the above required details.</p> <p>--</p>	<p>That means bidder has to quote complete cost for the said Item. if Client agreed to supply Sheet piles along with carriage then only contractor have to pay the Hire and carriage charges to client. otherwise contractor has to bear the cost.</p>

3	<p>As per the tender the submission date will be 15 days from the date of uploading of pre bid reply, we therefore request you to kindly extend the submission date by atleast 15 days as the prebid replies were uploaded on 27/11/2018.</p>	Refer corrigendum 3
4	<p>As the HFL of gandak river is provided along with prebid replies uploaded on 27/11/18, which is also with different datum (compare to LS of pipeline, Hydraulic process drawing of STP), we may require to do the preliminary survey of levels for submitting the tender, as the preliminaray survey and analysis of the same and designing the project accordingly is time taking process. We request you to kindly extend the bid submission date by atleast another 15 days.</p>	Refer corrigendum 3