



बिहार शहरी आधारभूत संरचना विकास निगम लि०, पटना (बिहार सरकार का एक उपक्रम)

नूतन राजधानी अंचल क्षेत्र बेउर, पटना- 800002

QUOTATION NOTICE

Memo No...../ Patna,


Date...../

Sealed quotation from reputed firms or intending persons are invited in the office of the undersigned for the work for **Laying of Cable from ACB to Staff Quarter Beur STP and Repalcement of Old & damaged 600AMP OCB by 800AMP ACB at Beur STP, Beur patna.** So, as to reach on or before **06.06.2020 upto 3.00 P.M.** The quotation will be opened on the same day at 4.00 P.M. in presence of the quotationers or their authorized representatives.

S. No.	Particular	Qty	Unit	Rate	Amount (Rs.)
1	Supplying C-Power L&T 800AMP ACB Draw out 4 pole EDO Breaking Capacity 50KA Micro processor Based SR 18G Cat No.- SL 96072 .	1	Each		
2	Supplying box of size 1800mm x 900mm x 900mm made of 14 SWG C.R sheet with all required Nos. of hole for fitting of 800 AMP ACB including locking arrangement with powder coating complete including ampere meter 96mm ² - 0-600amp, AVF Digital volt meter, C.T coil 0-600amp - 3 nos. selector switch, KEC- 2 nos, indicator Lamp big size- 6 nos.	1	Each		
3	Supplying for connection copper strip 50mm x 12mm section.	30	P.kg		
4	Supplying fitting Hyleum sheet or bush bar supporter and all required G.M Nut and Bolt.	1	P. item		
5	Earth work in excavation in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan) including etc.	22.50	PM ³		
6	Supply of Cable 95mm ² 3.5 core Aluminium conductor Armoud (Heavls) including carriage.	100	PM		
7	Laying of pipe.	100	PM		
8	Supplying and filling in plinth with local sand and under floors including, watering, ramming consolidating and dressing complete.	22.50	PM ³		
9	Thumble 95mm ²	24	Each		
10	Glass Tap	2	Each		
11	Supplying of MCCB DH 125 LT DH R- 56 to 63.	1	Each		
12	Supplying of cabnet of MCCB LTDH R- 50 to 63	1	LS		
13	Starter of 1HP sumpersible motor of pump house of Quarter.	1	Each		
14	Labour for fitting fixing all complete jobs.		LS		
15	400mm ² Aluminum conductor cable 3.5 core.	25	PM		
16	400mm ² Copper Thumble.	12	PM		
17	Gland Packing of Cable.	12	PM		
18	Foundation of ACB including E/W excavation and B/F soling and B/W (1:4), PCC (1:2:4) 0.15mm thick including carriage of materials all complete. (Size- 1M x 1M)		LS		

Terms & Conditions:-

1. Quoted rate should be including of all taxes as per Govt. rule applicable.
2. Attached Registration Copy, Pan card & GST.
3. Attached self Affidavit completion the work.


 Executive Engineer

Memo No...../Patna dated...../

Copy forwarded to Assistant Engineer/Junior Engineer, Buidco Buidco Nutan Rajdhani Anchal, Beur, Patna for information and necessary action.

EP/

Executive Engineer

Memo No...../Patna dated...../

Copy forwarded to Chief Engineer/ Supertending Engineer, PMC Buidco, Patna for information.

EP/

Executive Engineer

Memo No. 266...../Patna dated. 01-06-2020...../

Copy forwarded to I,T Manager, Buidco Patna for information and uploaded on buidco Website and necessary action.

EP/ 01.6.20

Executive Engineer
IT/2020